

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21047-00-00
Spot: N2NENE Sec/Twnshp/Rge: 9-33S-35W
660 feet from W Section Line, 4680 feet from W Section Line
Lease/Unit Name: RHODA SMITH Well Number: 1
County: STEVENS Total Vertical Depth: 6400 feet

Operator License No.: 31269
Op Name: BELCO ENERGY CORP.
Address: 5735 PINELAND STE 300
DALLAS, TX 75231

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1732 WITH 790 SX CMT
Production: Size 5.5 feet: 6400 WITH 480 SX CMT
Liner: Size _____ feet: \$208.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2001 9:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 5970' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1750' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 30 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/26/2001 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6188'. PERFS AT 6012-6032'. SET CIBP @ 5910' WITH 2 SX CMT ON TOP. LOAD HOLE WITH 9# MUD & CIRCULATE. 1ST PLUG AT 1750' WITH 50 SX CMT. 2ND PLUG AT 568' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 6 2001

CONSERVATION DIVISION

INVOICED

DATE 7-6-01

INV. NO. 20020616

Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 1863' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II
(TECHNICIAN)

JUL 02 2001

Form CP-2/3