

To: 1 020421
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-2015-189-00349-0000 2670
API NUMBER 15- Drill Completion Date 2/88

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: 2319 N. Kansas
Liberal, KS 67901

SE SE NW, SEC. 26, T. 33 S, R. 35 W/EK
2970 feet from S section line
2970 feet from E section line
Lease Name Heath "A" Well # 1
County Stevens 92.10
Well Total Depth 2834 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 640

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208
Address 2319 N. Kansas, Liberal, KS 67901

Company to plug at: Hour: 8:30 a.m. Day: 20 Month: 11 Year: 19 91

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-5530

were: 5 1/2" at 2831' w/600 sx, PBTD 2826', Perfs at 2650'-2790'

- 1st plug set CIBP at 2630' with 2 sx cement on top,
- 2nd plug run tubing to CIBP, circulate hole with gel mud, pump 10 sx cement at 1750'
- 3rd plug pump 50 sx cement at 690', cement to surface.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 20 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2630' with 2 sx cement on top,
2nd plug ran tubing to bottom, circulated hole with gel mud, pumped 15 sx cement
at 1750-1540',
3rd plug pumped 60 sx cement at 713' to surface.

RECEIVED
STATE CORPORATION COMMISSION
11-26-91
NOV 26 1991

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 8% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I did ~~not~~ observe this plugging.

DATE 12-9-91
INV. NO. 34040

Signed Glenn R. Barber (TECHNICIAN)