

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20736-00-01
Spot: CNW Sec/Twnshp/Rge: 27-33S-35W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: HILBIG 2A UNIT Well Number: 3
County: STEVENS Total Vertical Depth: 3200 feet

Operator License No.: 3037
Op Name: MOBIL EXPL. & PROD. NORTH AMERI
Address: PO BOX 4358
HOUSTON, TX 77210

Production Casing Size: 5.5 feet: 3190 410 GEL & 125 SX CMT
Surface Casing Size: 8.625 feet: 1744 WITH 575 SX CMT
\$104.00

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/18/2003 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS WITH 25 SX CMT. PUMP MUD TO 1750'. PUMP 25 SX CMT INSIDE 5 1/2". 40 SX CMT AT 600'. 10 SX CMT AT 40'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/19/2003 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PERFS AT 2700-20 & 2730-45'. CIBP @ 2790'. PUMP 400# HULLS WITH 25 SX CMT FOR BOTTOM PLUG. PUMP 17 1/2 BBL MUD (TOTAL WITH HULLS & AFTER BOTTOM 25 SX CMT) TO 1750; PUMP 25 SX CMT INSIDE 5 1/2". LOAD HOLE WITH MUD. SDON. 02/19/2003: PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED
FEB 28 2003
KCC WICHITA


Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 824' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II
(TECHNICIAN)



INVOICE
DATE 2-28-03
INV. NO. 2003061250