

1 020322

7-12

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,389 - 0000

C NW NW, SEC. 30, T 33 S, R 35 W/E

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Nix "A" Well # 1-30

Operator: McCoy Petroleum Corporation

County Stevens 216.09

Name & Address

110 S. Main, Suite 500

Well Total Depth 6649 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1740

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor McCoy Petroleum License Number 5003

Address 110 S. Main, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 12 Month: 7 Year: 19 90

Plugging proposal received from Daryl Hanson

(company name) McCoy Petroleum (phone) 316-356-3510

were: 4 1/2" at 3298' w/325' sx cement, PBDT 3550', Perfs at 2995-98, 3008-10, 3014-24', TOC @ 1670'

1st plug set CIBP at 2550' and dump 3 sx cement on top of sand through bailer,

2nd plug circulate with gel at cut off and pump 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40-0' with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-18-90  
JUL 18 1990

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 5:30 p.m. Day: 12 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500' with 2 sx cement on top,

Loaded hole with mud,

2nd plug at 1650' with 50 sx cement,

3rd plug at 690-497' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1650' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-24-90

Signed Glenn R. Larkins (TECHNICIAN)

INV. NO. 28718