

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21959-00-00
Spot: CNE Sec/Twnshp/Rge: 35-33S-35W
3960 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: SCHWEITZER G F Well Number: 35-2
County: STEVENS Total Vertical Depth: 2900 feet

Operator License No.: 4742
Op Name: TEXACO EXPL. AND PROD. INC.
Address: PO BOX 277
VELMA, OK 73491

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 617 WITH 375 SX CMT
Production: Size 4.5 feet: 2899 WITH 525 SX CMT
Liner: Size _____ feet: _____ 294.25

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/22/2001 2:30 PM
Plug Co. License No.: 31705 Plug Co. Name: H & K PLUGGING AND SALVAGE
Proposal Rcvd. from: JIM CONNER Company: H & K PLUGGING AND SALVAGE Phone: (806) 665-2550

Proposed Plugging Method: CIBP @ 2624' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1600' WITH 30 SX CMT. 2ND PLUG AT 650' WITH 30 SX CMT. 3RD PLUG AT 60' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/22/2001 6:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2852'. SET CIBP @ 2624' WITH 2 SX CMT ON TOP BY DUMP BAILER. RAN 2 3/8" TUBING IN HOLE TO 1600'. LOADED HOLE WITH MUD. PUMPED CMT DOWN 8 5/8" X 4 1/2" ANNULUS 45 SX CMT. MAXIMUM PRESSURE 500#. PUMPED DOWN 2 3/8" 30 SX CMT AT 1600'. PULLED TO 650' PUMPED 30 SX CMT. PULLED UP TO 60' PUMPED 15 SX CMT.

INVOICED
DATE 5-31-01
INV. NO. 2001061871

RECEIVED
KANSAS CORPORATION COMMISSION
5-31-01
MAY 31 2001
CONSERVATION DIVISION

Remarks: USED CLASS A CMT BY H & K PLUGGING. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

MAY 30 2001

Form CP-2/3