

15-191-00438-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Summer County. Sec. 21 Twp. 30 Rge. 4 (X) (W)
Location as "NE/CNW/SW" or footage from lines. SW SW SE
Lease Owner Aylward Drilling Company
Lease Name Kirk Well No. 1
Office Address 813 1st Natl. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 14 19 57
Application for plugging filed December 14 19 57
Application for plugging approved December 14 19 57
Plugging commenced December 14 19 57
Plugging completed December 14 19 57
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham, Winfield, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4752 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 225'; cement plug of 15 sacks of cement; heavy mud to 35'; cement plug of 10 sacks of cement to top of surface.

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1957
VISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st Natl. Bank Bldg. - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Paul W. Hesse (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Natl. Bank Bldg. - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 57

My commission expires February 27, 1960
Mildred F. Willis Notary Public.

PLUGGING
FILE SEC 21 T 30 R 4W
BOOK PAGE 69 LINE 14

KIRK NO. 1

Casing Record:

Company: Aylward Drilling Company
Contractor: Aylward Drilling CompanyLocation: SW SW SE 21-30-4W
Sumner County, Kansas

8 5/8" - 230'

Commenced: November 28, 1957
Completed: December 14, 1957

Elevation: 1473 KB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Gravel	0	40	Set 8 5/8" surface pipe @ 230' w/200
Sand	40	100	sacks cement
Red Rock	100	350	
Shale	350	640	GEOLOGICAL TOPS:
Salt	640	730	Stalnaker Zone 3230
Shale & Shells	730	850	Stalnaker Sand 3248
Lime & Shale	850	1875	Lansing 3517
Sand & Shale	1875	2090	Mississippian 4142
Shale with lime	2090	2245	Kinderhook 4530
Shale & Lime	2245	2470	Simpson 4588
Shale with some Lime	2470	2623	Arbuckle 4696
Shale & Lime	2623	2902	RTD 4752
Lime & Shale	2902	3005	
Shale & Lime	3005	3090	
Shale	3090	3217	DST 4163-4180 Open 1 hr. Wk. bl.
Shale with some Sand	3217	3383	Rec. 325' SW. 1BHP 1620#, FBHP 1265#
Shale & Lime	3383	3507	IFP 0# - FFP 146#.
Shale	3507	3517	
Lime	3517	3742	
Lime & Shale	3742	4014	
Shale & Lime	4014	4084	
Lime & Shale	4084	4141	
Lime	4141	4307	
Cherty Lime with Shale	4307	4330	
Chert & Lime	4330	4390	
Cherty Lime	4390	4447	
Chert & Lime	4447	4498	
Lime	4498	4525	
Lime & Shale	4525	4558	
Cherty Lime & Shale	4558	4592	
Sand	4592	4649	
Lime & Shale	4649	4677	
Sand	4677	4700	
Lime	4700	4749 T.D.	

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1957
OIL DIVISION
Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 17th day of December, 1957

Mildred F. Willis
Notary Public

My Commission expires: February 27, 1960.

PLUGGING
FILE SEC 21 T 30R 4W
BOOK PAGE 69 LINE 14