

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SE

SEC. 24 TWP. 29S RGE. 1W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease McKnab

Operator E. H. Adair Oil Co. Address 1017 E. Second
Wichita, Kansas

Field Wildcat County Sedgwick

Total Depth 3370 Feet.

Plugging Contractor _____ Company tools _____

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

269 feet of 8-5/8" surface pipe circulated with cement. 5-1/2" set at

3360 feet. Perforations from 3344 to 3330. Plug set at 3350 feet.

Set plug and 5 sacks of cement at 3330 feet. Shot off and pulled casing

and filled hole with heavy mud to 269 feet. Set plug and 15 sacks of cement

at 269 feet. Mudded hole to 20 feet of surface; set plug and 5 sacks of

cement to surface.

District Conservation Agent

Date October 19, 1955

PLUGGING
FILE SEC. 24 TWP. 29S R. 1W
BOOK PAGE 9 LINE 29