

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-191-21,069-0000

LEASE NAME Russell

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Bear Petroleum, Inc.

SEC. 35 TWP. 30 RGE. 2 (E) or (W)

ADDRESS Box 438, Haysville, KS 67060

COUNTY Sumner

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Date Well Completed 9-6-80

Character of Well Oil

Plugging Commenced 10-5-98

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-9-98

The plugging proposal was approved on 9-16-98 (date)

by Luthy (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? yes

Producing Formation Mississippi Depth to Top 3772 Bottom 3776 T.D. 3814

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content Surface	From surf	To 453	Size 8 5/8	Put in 453	Pulled out 0
	Production	surf	3814	4 1/2	3814	2215

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Dumped sand from PBTD 3785' to 3726', dump bailed 4 sax cement, shot pipe off at 2215' and pulled, ran tubing to 453', spotted 35 sax, pulled tubing to 250', circulated cement to surface and pulled tubing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004

Address Box 607, Burrton, KS 67020 10-15-98

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

R.A. Schremmer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 438, Haysville, KS 67060

Subscribed and sworn to before me this 14th day of October, 19 98

[Signature]
Notary Public

My Commission Expires: April 15, 1999

