

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sumner SEC. 13 TWP. 305 RGE. 2 NE/W
Location as in quarters or footage from lines:
SW-NW-NW

	X		

Lease Owner Hummon Corp.
Lease Name Meredith Well No. 2
Office Address 400 One Main Place, Wichita
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 4-1-69
Application for plugging filed July 7, 1983
Plugging commenced 8-24-83
Plugging completed 8-26-83
Reason for abandonment of well or producing formation
No Production

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Glenn Ward
Producing formation K.C. Depth to top 3197 bottom T.D. 4347
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				85/8	252	none
				5 1/2 3/8	4291	120
					3210	267


Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

5 1/2" Model D Baker permanent packer set @ 3210: 2' tubing to 267
Foot, unable to pull tubing. 5 1/2 casing to 120' unable to pull
casing. Pumped 600 sacks cement in, surface cement settled to
240; filled surface pipe with ready mix to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
DEWEY GRESSEL (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Dewey Gressel
(Address) _____

SUBSCRIBED AND SWORN TO before me this 2 day of Nov, 19 83

Gary D. Stearns
Notary Public.

My Commission expires: Aug 4, 1984

RECEIVED
STATE CORPORATION COMMISSION

11-4-83

NOV 4 1983

CONSERVATION DIVISION
Wichita, Kansas

15-191-2018-0000

WELL LOG
Meredith # 2
SE NW NW 13-30S-2W
Sumner County, Kansas

<u>FROM</u>	<u>TO</u>		Elevation 1321' K.B.
0	266	Soil & shale	
266	3093	Shale & Lime	
3093	3290	K.C. Lime	
3290	3733	Lime & Shale	
3733	4075	Miss. Lime	
4075	4143	Lime & Shale & Sand	
4143	4235	Simpson Sand	
4235	4347	Arb.-Lime	
4347		Total Depth	

STATE OF KANSAS
COUNTY OF BARTON ss

T. D. Sweetman, President of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman
T. D. Sweetman

Subscribed and sworn before me this 17th day of February, 1969.

RECEIVED
STATE CORPORATION COMMISSION

JUL 0 8 1983

CONSERVATION DIVISION
Wichita, Kansas

Leata S. Boyd
Notary Public Barton County

