

15-191-00176-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 9-23-68  
LEASE NAME McLAUGHLIN  
WELL NUMBER 2 2 1  
300 Ft. from S Section Line  
300 Ft. from E Section Line  
SEC. 11 TWP. 30 SRGE. 2 R50 or (W)  
COUNTY SUMNER  
Date Well Completed 9-23-68  
Plugging Commenced 7-27-88  
Plugging Completed 7-29-88  
Did you notify the KCC District Office prior to plugging this well? yes

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR HUMMON CORPORATION  
ADDRESS 400 ONE MAIN PLACE WICHITA, KS 67202  
PHONE # 316) 263-8521 OPERATORS LICENSE NO. 5050  
Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Which KCC Office did you notify? WICHITA  
Is ACO-1 filed? N/A If not, is well log attached? Yes  
Producing Formation KC Depth to Top 3202 Bottom 3205 T.D. 4156  
Show depth and thickness of all water, oil and gas formations. P.B. t.d. 3386

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
<u>STATE CORPORATION COMMISSION</u> <u>AUG = 4 1988</u>	<u>8-4-88</u>	<u>surface</u>	<u>313</u>	<u>8 5/8"</u>	<u>313'</u>	<u>none</u>
		<u>surface</u>	<u>3421</u>	<u>5 1/2"</u>	<u>3421'</u>	<u>1570'</u>

Describe in detail manner in which the well was plugged, indicating where the mud fluid was placed and methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
SAND BACK TO 3176'. DUMPED 5sks CEMENT W/DUMP BAILER. SHOT PIP OFF @ 1570'  
PULLED PIPE. BAILED DOWN TO 370' BUILT ROCK BRIDGE. READY MIX TO SURFACE.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GRESSEL CORPORATION License No. 5822  
Address p.o. box 322 HAYSVILLE, KS 67060  
STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Byron E. Hummon, Jr. ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX~~ (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Byron E. Hummon, Jr.*  
(Address) 400 One Main Place, Wichita, KS 67202



SWORN TO before me this 3rd day of August, 19 88

*Sandra L. Mendoza*  
Notary Public

My Commission Expires: February 13, 1990

WELL LOG  
McLaughlin Washdown  
11-30S-2W  
Sumner County, Kansas

15-191-00176-0001

<u>FROM</u>	<u>TO</u>	
3772	3806	Shale
3806	4074	Miss. Lime
4074	4152	Lime and shale
4152	4156	Sand
4156		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss


T. D. Sweetman, President of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

  
T. D. Sweetman

Subscribed and sworn before me this 26th day of September, 1968.

  
Notary Public ~~Barton County~~ COMMISSION

My Commission Expires 5-9-71



JUL 11 1988

CONSERVATION DIVISION  
Wichita, Kansas

15-191-00176-0001

WELL LOG  
McLaughlin Washdown  
11-30S-2W  
Sumner County, Kansas

FROM	TO	
3772	3806	Shale
3806	4074	Miss. Lime
4074	4152	Lime and shale
4152	4156	Sand
4156		Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 4 1988

STATE OF KANSAS  
COUNTY OF BARTON ss


CONSERVATION DIVISION  
Wichita, Kansas

T. D. Sweetman, President of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman  
T. D. Sweetman

Subscribed and sworn before me this 26th day of September, 1968.

Reata L. Boyd  
Notary Public Barton County



Commission Expires 5-9-71