

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

JAN 29 1963

CONSERVATION DIVISION
7/6
1/29/63Operator's Full Name Santa Fe Pipe and SupplyComplete Address: Box 562, Great Bend, KansasLease Name Rose Well No. # 1Location NW NW NE Sec. 27 Twp. 28 Rge. 11 (E) (W)WCounty Pratt Total Depth 4601Abandoned Oil Well x Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Glen and Smith Pipe Pulling Co.Address: Box 156, Ellinwood, Kansas License No. 396Operation Completed: Hour 12:00PM Day 25th Month Jan. Year 1963

The Above well was plugged as follows:

310' of 8 5/8" surface pipe circulated with cement. 4553' of 5 1/2" long
string cemented with 125 sacks cement. Plugged back to 4370'. Top of
perferation 4337', sanded to 4330' cemented with 5 sacks. Filled hole
to 200' and 10' rock bridge, cemented with 20 sacks. Filled hole to 40'
and a 10' rock bridge cemented with 10 sacks to base cellar.
1886' of 5 1/2" long string pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Annie Elving
Well Plugging SupervisorDATE 1/29/63
INV. NO. 6488-11