

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-189-10086-0000

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1966
7-12-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern Pipe Line has this date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828, Liberal, Kansas

Lease Name: Spikes Well No. 1-7

Location: Center Sec. 7 Twp. 31 Rge. 37 (E) (W)

County Stevens Total Depth 2624' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

10 3/4" to 525' circulated w/ cement. 7" to 2417' circulated w/ cement.

4 1/2" to 2353' on a packer. No perforations

Plug bottom w/ 60 sacks cement. Top of cement 2390'

Mud 2390' to 600' Spotted 40 sacks cement 600' to 400'

Mud 400' to 100' Plug, Hulls & 20 sacks cement 100' to 0'

Very truly yours,

E. Edward Jones
Conservation Division Agent