



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Building  
WICHITA, KANSAS 67202  
RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1971

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-189-10013-0000

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Laird of Mesa Pet. has this

date requested permission to plug the following described well:

Mr. Laird guarantees payment of the plugging fee.

Operator's full Name: Mesa Petroleum Company

Complete Address: Box 2009, Amarillo, Texas

Lease Name: Grey Well No. 2-11

Location: S/2 NE NE Sec. 11 Twp. 31 Rge. 38 (E) (W)

County: Stevens Total Depth 5756' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Laird was instructed to plug the well as follows:

13 3/8" to 515' circulated w/ cement. 8 5/8" to 2994' cemented.

Top perforations 2694' Plug bottom w/ 400 sacks cement.

Top of cement 2290' Mud 2290' to 160'

Spot 35 sacks cement 1608' to 1508' Mud 1508' to 995'

Spot 35 sacks cement 995' to 8950' Mud 895' to 60'

Plug, Halls & 15 sacks cement 60' to 0'.

Very truly yours,

*Edgar J. Lewis*  
Conservation Division Agent