



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-189 - 10162-0000

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1964  
9-21-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Kuhn of Walter Kuhn Drilling Co. has this  
date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: Walter Kuhn Drilling Co.

Complete Address: 726 Union Center, Wichita, Kansas

Lease Name: Curtis Well No. # 1

Location: C NE Sec. 25 Twp. 31 Rge. 39 (E) (W)

County Stevens Total Depth 2622' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

10 3/4"-530' Circulated w/cement. 5 1/2"-2405' 7"-2405'

Packer 2399' to 2405'. 5 1/2" linner 2405' to 2620'

Sand bottom w/sand to 2441' 20 Sax.cement top cement 2292'

Mud 2292' to 530' Spotted 35 Sax.cement 530' to 450'

Mud 450' to 25' Plug,Hulls,15 Sax.cement 25' to 0

Very truly yours,

*[Signature]*  
Conservation Division Agent