

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

JUL 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

15-189-30103-0008

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Simmons "B" Well No. 2

Location: SE NW SW Sec. 25 Twp. 31 Rge. 39 (w)

County Stevens Total Depth 2900' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 608' circulated w/ cement. 5 1/2" to 2898' circu. w/ cement.

Top perforations 2703 Plug bottom w/ 15 sacks cement.

Top of cement 2560' Mud 2560' to 600'

Spot 20 sacks cement 600' to 440' Mud 440' to 40'

Plug & 5 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent