

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)
15-189-16006-0001

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas 67901

Lease Name: Simmons "B" Well No. 1

Location: C SW Sec. 25 Twp. 31 Rge. 39 (E) (W)

County Stevens Total Depth 3029' Oil Well

Gas Well Input Well SWD Well X D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 626' circulated w/ cement. 4 1/2" to 2913' ciru. w/ cement.

Top perforations 1253' Plug bottom w/ 10 sacks cement

Top of cement 1100' Mud 1100' to 625'

Spot 10 sacks cement 625' to 525' Mud 525' to 50'

Plug & 5 sacks cement 50' to 0'.

Very truly yours,

Conservation Division Agent