



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-10124-00-01

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Trigg has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Trigg Exploration

Complete Address: 410 Woolworth Bldg, Boulder, Colorado

Lease Name: Milburn Well No. CL-16

Location: C NE SW Sec. 16 Twp. 31 Rge. 40 (E) (W)

County: Morton Total Depth 5680' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1767' circulated w/ cement. 5 1/2" to 5535' cemented.

Top perforations 5324' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent