



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-129-00073-0000

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Woolridge of Pan American has this

date requested permission to plug the following described well:

Mr. Woolridge guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporations

Complete Address: Box 432, Liberal, Kansas 67901

Lease Name: Wratil Gas Unit "B" Well No. 1

Location: SW NE Sec. 22 Twp. 31 Rge. 40 (E) (W)

County: Morton Total Depth 6085' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Woolridge was instructed to plug the well as follows:

8 5/8" to 1718' circulated w/ cement. 5 1/2" to 6030' cemented.

Top perforations 5202' Plug bottom w/ Bridge Plug & 2 sacks cement.

Top of cement 5146' Mud 5146' to 1743'

Spotted 20 sacks cement 1743' to 1693' Mud 1693' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves  
Conservation Division Agent