



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-129-10140-0000

APR 27 1964

4-27-64  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir: Pan American Petroleum Corp. sold this well to  
 Fender Pipe & Supply Inc. Russell, Kansas  
 Mr. Goodstead of Pan American Petroleum Corp. has this  
 date requested permission to plug the following described well:

Mr. Goodstead guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corp.

Complete Address: Box 432 Liberal, Kansas

Lease Name: Winter Gas Unit "C" Well No. # 1

Location: C SW NE Sec. 27 Twp. 31 Rge. (E) (W) L0

County Morton Total Depth 6050' Oil Well x

Gas Well    Input Well    SWD Well    D & A x Lost Hole   

Mr. Goodstead was instructed to plug the well as follows:

8 5/8" - 698' Cir. w/cement. 5 1/2" - 6050' Cemented. Perforations 5526' to 5530'

Plug bottom w/10 Sax. cement top cement 5420' Mud 5420' to 600'

35 Sax. cement 600' to 500' Mud 500' to 55'

Rock bridge 55' to 45' 15 Sax. cement 45' to 0

Very truly yours,

*[Signature]*  
 Conservation Division Agent