



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-10166-0000

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1971

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dungan of Superior Oil has this

date requested permission to plug the following described well:

Mr. Dungan guarantees payment of the plugging fee.

Operator's full Name: Superior Oil Company

Complete Address: Box 200, Casper, Wyoming

Lease Name: Hume Unit Well No. 1

Location: C NE Sec. 5 Twp. 31 Rge. 42 XE (W)

County: Morton Total Depth 5331' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Dungan was instructed to plug the well as follows:

10 3/4" to 1531' circulated w/ cement. 7" to 5331' cemented.


Top perforations 5237' Plug bottom w/ 25 sacks cement.

Top of cement 5100' Mud 5100' to 800'

Spot 60 sacks cement 800' to 700' Mud 700' to 40'

Plug, Halls & 20 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent