



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)
15-129-20150-0003

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Radke of Terra has this

date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Terra Resources Inc.

Complete Address: Box "C" , Great Bend, Kansas

Lease Name: Terra-Wilson Hanke Well No. 1

Location: 1840' FEL & 790' FSL Sec. 7 Twp. 31 Rge. 42 (E)(W)

County: Morton Total Depth 5800' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Radke was instructed to plug the well as follows:

8 5/8" to 1528' circulated w/ cement. Mud 5800' to 2900'

Spot 100 sacks cement 2900' to 2600' Mud 2600' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent