



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-175-00457-0000

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this
date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Morgan Well No. 1

Location: C NE Sec. 31 Twp. 31 Rge. 32 ~~(E)~~ (W)

County: Seward Total Depth 2760' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 620' circulated w/ cement. 4 1/2" to 2756' cemented.


Top perforations 2648' Plug bottom w/ 20 sacks cement.

Top of cement 2300' Mud 2300' to 600'.

Spot 35 sacks cement 600' to 500'. Mud 500' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent