

State of Kansas



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1962  
7-13-62  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-175-10128-0000

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date 10 July, 1962, authorized

The following plugging operation:

Operator's full Name: Texaco Inc.

Complete Address: 210 North Kansas, Liberal, Kansas

Lease Name: Anna Day Well No. 1

Location: C SWSE Sec. 6 Twp. 31S Rge. 34 (W)

County Seward Total Depth: 5730

Oil Well  Gas Well  Input Well  SWD Well

D & A  Other well as hereafter indicated:

Operator was instructed to plug well as follows:

85/8" 622' circulate w/cem.

Heavy mud 5730 to 2700

Cem. 70 sax. 2700' to 2450'

Heavy mud 2450' to 620'

Cem. 30 sax. 620' to 530' Mud 530' to 30' Cem. 10 sax. to top of hole.

Very truly yours,

*Fligh Scott*

