

State of Kansas



15-175-10129-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1966
8-20-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco, Inc. has this

date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco, Inc.

Complete Address: 614 Biltling Bldg, Wichita, Kansas

Lease Name: Anna Day O/A Well No. 2

Location: C SW NE Sec. 6 Twp. 31 Rge. 34 (W)

County Seward Total Depth 5550' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

8 5/8" to 633' circulated w/ cement. 5 1/2" to 5550' cemented.

Top perforations 5398' Plug bottom w/ 25 sacks cement .

Top of cement 5200' Mud 5200' to 650'

Spotted 35 sacks cement 650' to 550' Mud 550' to 30'

Plug, Hulls & 10 sacks cement 30' to 0'.

Very truly yours,

Edward J. Green
Conservation Division Agent