



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-175-10117-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mobil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Company

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Marguerite Rooney Unit Well No. 2

Location: 150' S C NE SW Sec. 7 Twp. 31 Rge. 34 XX (E) (W)

County: Seward Total Depth 5700' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 643' circulated w/ cement. 4 1/2" to 5500' cemented.


Top perforations 5412' Plug bottom w/ 20 sacks cement .

Top of cement 5200' Mud 5200' to 643'

Spot 35 sacks cement 643' to 543' Mud 543' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent