



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

28 September 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-025-20523-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT - 1 1981

Dear Sir:

Mr. Earl Evers of Bogger Petroleum Inc. ^{Wichita, Kansas} this

date requested permission to plug the following described well:

Operator's Full Name: Bogger Petroleum Inc.

Complete Address: 802 Petroleum Building 1110, 16th, Denver Colo. 80202

Lease Name: alley Well No. 36-13

Location: SW SW Sec. 36 Twp. 31S Rge. 24W (E) (W)

County: Clark Total Depth: 5540'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Evers was instructed to plug the well as follows:

There is 619' of 8 5/8" surface casing cement circulated with 200 lbs of
Halliburton ^{lite} + 150 lbs of common with 2 1/2 Jell + 3% cc cement.

The anhydrite was 12.50' to 15.20' circulated for 10 min at 1000' with
heavy mud. 1st plug at 1000' with 50 lbs cement 2nd plug pushed rubber
plug to 600' then put 15 lbs bulls + 35 lbs of cement on top of rubber
plug. 3rd plug on solid bridge at 40' to 0' with 10 lbs cement. Then
put 5 lbs in rat hole + 5 lbs in mouse hole. Plugging
accomplished by Halliburton Co.

Very truly yours,

Paul Luthis
Conservation Division Agent