



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

17-February 1982

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-025-20,570-0000

Dear Sir:

Mr. Bud Werrick of Murfin Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Murfin Drilling Co

Complete Address: 617 Union Bldg Wichita Kansas 67202

Lease Name: Inlow Well No. 1-23

Location: NW-NW-SE Sec. 23 Twp. 31 Rge. 25W (E) (W)

County: Clark Total Depth: 5823'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Werrick was instructed to plug the well as follows:

There was 40' of 22" conductor & 580' surface casing cement circulated. The surface casing was cemented with 350 lbs of cement. The hydrate was topped at 1046'. 1st plug 930' with 50 lbs of cement. 2nd plug pushed rubber plug to 560' with 35 lbs of cement pumped on top of it. 3rd plug 40' to 0' on solid bridge with 10 lbs of cement. They circulated 10 lbs of cement in rat hole & 5 lbs of cement in mouse hole. The cement was pumped through

Very truly yours,

Paul Luther  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
2-23-82  
FEB 23 10 57  
CONSERVATION DIVISION  
Wichita, Kansas

*over*

with the hole full of heavy mud. The cement used  
was common cement with 2% Jell & 3% C.C.. The  
plugging was accomplished by allied cementing.

NEW YORK  
F B E C F  
1922