

*10*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-119-10084-0000

RECEIVED  
STATE CORPORATION COMMISSION

APR 24 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Wm. Gruenerwald

Complete Address: 35 E. Wacker Dr. Chicago, Ill.

Lease Name \_\_\_\_\_ Miles \_\_\_\_\_ Well No. # 1

Location SE/4 Sec. 7 Twp. 31S Rge. 29 (E) (W)

County Meade Total Depth 5485'

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5 PM Day 22 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 1673' Circulated w/cement. 5 1/2" 5485' Cemented. Top Perforation, 5444'

Plug bottom w/20 Sax.cement 5485' to 5335' Mud 5335' to 700'

Plug, 35 Sax.cement 700' to 600' Mud 600' to 40'

Plug, 15 Sax.cement 40' to surface. Weld Cap On Surface. Company Pump.

Pulled 3542' 5 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/24/63

INV. NO. 6960-w

Signed: *[Signature]*  
Well Plugging Supervisor