

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1974
CONSERVATION DIVISION
Wichita, Kansas
-15-119-20155-0050

Operator's Full Name National Oil Co.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Miles Well No. 1

Location C W/2 SE Sec. 7 Twp. 31 Rge. 29 (E) (W)

County Meade Total Depth 5500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Bruce Drilling Co.

Address Liberal, Kansas License No.

Operation Completed: Hour 4:30Pm Day 19 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 1417' circulated w/ cement. 4 1/2" to 5499' cemented.

Top perforations 5083' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 1400'

Spotted 35 sacks cement 1400' to 1235'. Mud 1235' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Halliburton Pump

Pulled 2654' of 4 1/2" casing. -u

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

DATE 7/2/74

INV. NO. 9424-U

INVOICED