

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Authority Aug 11, 1981
API Number 15-184-20, 501-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Texaco Inc.

Complete Address PO Box 2420 Tulsa Okla 74102

Lease Name Moscow Sw Disposal Well No. 1

Location 50' FSL - 75' FWL - SE SE Sec. 29 Twp. 31 Rge. 36 (East) (West)

County Stevens Total Depth 1540

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Liberal Kans License No. 511

Operation Completed: Hour: 2:00 PM Day: 26 Month: Aug Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There was 650' of 8 5/8" surface casing. C.C.
5 1/2" casing set to 1300; 3 1/2" line slotted
set to 1300-1450; 2 3/8" slotted liner set from
1439-1540. 1st plug on bottom with 30
lbs cement. 2nd plug at 750-450 with 50
lbs cement. 3rd plug at 60-0 with 10 lbs
cement. 5 1/2" was circulated with 350 lb
cement. No salvage

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1981
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1981 8-30-81

I hereby certify that the above well was plugged as herein stated

INVOICED
DATE 9-25-81
INV. NO. 7454W

Signed: Thomas Thomas
Conservation Division Agent