

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-189-10086-0000

RECEIVED  
STATE CORPORATION COMMISSION  
7-12-66  
JUL 12 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Co.

Complete Address: Box 828, Liberal, Kansas

Lease Name Spikes Well No. 1-7

Location Center Sec. 7 Twp. 31 Rge. 37 (X) (W)

County Stevens Total Depth 2624'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 9 Month 7 Year 1966

The Above well was plugged as follows:

10 3/4" to 524' circulated w/ cement. 7" to 2417' circulated w/ cement.

4 1/2" to 2353' on a packer. No perforations

Plug bottom w/ 60 sacks cement. Top of cement 2390'

Mud 2390' to 600' Spotted 40 sacks cement 600' to 400'

Mud 400' to 100' Plug, Hulls & 20 sacks cement 100' to 0'

Pulled 2353' of 4 1/2" casing & packer. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/12/66

INV. NO. 3545-W