

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mesa Petroleum Company 15-189-10013-0000

Complete Address Box 2009, Amarillo, Texas 79105

Lease Name Grey Well No. 2-11

Location S/2 NE NE Sec. 11 Twp. 31 Rge. 38 (E) (W)

County Stevens Total Depth 5756'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Halliburton Cementing Co.

Address Liberal, Kansas License No.

Operation Completed: Hour 6:00PM Day 30 Month 8 Year 1971

The above well was plugged as follows:

13 3/8" to 515' circulated w/ cement. 8 5/8" to 2994' cemented.

Top perforations 2694' Plug bottom w/ 400 sacks cement.

Top of cement 2290' Mud 2290' to 1608'

Spotted 35 sacks cement 1608' to 1508' Mud 1508' to 995'

Spotted 35 sacks cement 995' to 895' Mud 895' to 60'

Plug, Hulls & 15 sacks cement 60' to 0'. Halliburton Pump Truck.

No Pipe Pulled.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Lewis*
Well Plugging Supervisor

INVOICED

DATE 9-2-71

INV. NO. 4276-W