

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 7 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Fieser "E" Well No. # 1

Location: C NW SE Sec. 18 Twp. 30 Rge. 5 (E) (W) W

County Kingman Total Depth 4610 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

226' of 8 5/8" surface pipe, cemented with 160 sacks. Fill
hole with drilling mud to 225', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent