

1090385

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,732-0050
S₂S₂ NW₄ SEC. 15, T 31 S, R 27 W/XX

TECHNICIAN'S PLUGGING REPORT

2970 feet from S section line
3960 feet from E section line

Operator License # 5152

Lease Name CHENEY Well # 1

Operator: Lee Banks

County MEADE Elev. 2446 GL

Name & Address 200 W. Douglas #550

Well Total Depth 5700 (MISS) 185.25 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8⁵/₈" feet 1433 KB

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Rine Drilling Co. License Number 5654

Address 300 W. Douglas, #600, Wichita, KS 67202

Company to plug at: Hour: 2:30 a.m. Day: 5 Month: Nov. Year: 19 85

Plugging proposal received from Lloyd Hubbard

(company name) Rine Drilling Co. (phone) 316-267-1333

were: to load the hole with mud and spot plugs through tubing as follows:

1st plug at 1475 feet with 80 sacks of cement

2nd plug at 612 feet with 40 sacks of cement

3rd plug at 40 to 0 on a solid bridge of hulls, wiper plug and 10 sacks of cement to the surface. 4th plug in the rathole with 15 sacks of cement and 5th plug in the mousehole with 10 sacks cement.

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 5:00 a.m. Day: 5 Month: NOV. Year: 19 85

ACTUAL PLUGGING REPORT Spotted the following plugs through drill pipe in heavy mud:

1st plug at 1475' with 80 sacks; 2nd plug at 612' with 40 sacks and 3rd plug from 40' to 0' on a solid bridge with 10 sacks cement. 4th plug in the rathole with 15 sacks circulated with a joint of pipe and 5th plug in the mouse hole with 10 sacks circulated.

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1985

11-8-85

Remarks: Cementing by Halliburton using 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form for CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(XXX) (do not) observe this plugging.

DATE NOV 22 1985

Signed Robert B. Tarbutton
(TECHNICIAN)

INV. NO. 11101