

To: 1 020669  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-29 API NUMBER 15-Drilled 8/615-189-10021-0000

S/2 SW NE, SEC. 1, T. 31 S, R. 35 W/E

2038 feet from N 1/4 section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Cutter Well # 2

Operator: Mobil Oil Corporation

County Stevens

Name & Address 2319 N. Kansas

Well Total Depth 5735 186.39 feet

Liberal, KS 67901

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 647

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 29 Month: 4 Year: 19 93

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 5 1/2" at 5731' w/550 sx cement, PBSD 5646', Perfs at 5570-5620', 5283-5300',

DV tool set at 3042', 700 sx cement circulated

1st plug run tubing to 1780', load hole with mud and pump 20 sx cement at 1780',

2nd plug pump 35 sx cement at 700',

3rd plug pump 5 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 29 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1780', loaded hole with mud, and pumped 20 sx cement at 1780',

2nd plug pumped 35 sx cement at 700',

3rd plug pumped 5 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton. No casing recovery. tubing sand in @ 1780'

(if additional description is necessary, use BACK of this form.)

I (did ~~XXXXXX~~) observe this plugging.

DATE 5-14-93

WELL NO. 37211

Signed Glenn R. Barlow  
(TECHNICIAN)