

To: 1 020655  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

AP.I NUMBER 15- Drilled 8/62/89 - 10040-0301

NE SW, SEC. 1, T 31 S, R 35 W/E  
1980 feet from S section line  
1980 feet from W & section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: 2319 N. Kansas  
Liberal, KS 67901

Lease Name H.F. Brown Well # 2  
County Stevens 182.48  
Well Total Depth 5615 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 578

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2:30 p.m. Day: 8 Month: 4 Year: 1993

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 5615' w/1050sx cement, PBD 4759', Perfs at 4714-50, 4614-23'  
Retrievable Bridge Plug at 4680' left in hole

1st plug load hole with mud and shoot tubing at 4523', pump 1 sx hulls and 20 sx cement,  
2nd plug pump 20 sx cement at 1780',  
3rd plug pump 32 sx cement at 650', 4th plug pump 8 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_  
Operations Completed: Hour: 3:15 p.m. Day: 9 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug loaded hole with mud and shot tubing at 4523'. Pumped 1 sx hulls and 20 sx cement, displaced with mud,  
2nd plug pumped 20 sx cement at 1780',  
3rd plug pumped 32 sx cement at 650',  
4th plug pumped 8 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION

4-14-93 APR 14 1993

Remarks: Used common cement by Sargent & Horton. No casing recovery. Recovered 4523' of 2 3/8" tubing.  
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 4-22-93

Signed Glenn R Barlow  
(TECHNICIAN)

INV. NO. 37603