

To: 1 020666 4-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,093-00-01 119A  
NW NE, SEC. 1, T. 31 S, R. 35 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: 2319 N. Kansas  
Liberal, KS 67901

4520 feet from S section line  
2080 feet from E section line  
Lease Name Cutter Well # 5  
County Stevens 185.25  
Well Total Depth 5700 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 664

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 3 p.m. Day: 27 Month: 4 Year: 1993

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 5 1/2" at 4745' w/175 sx cement, PBTD 4707', Perfs at 4580-88', 4623-30'  
1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud,  
2nd plug pump 25 sx cement at 1780',  
3rd plug pump 45 sx cement at 700',  
4th plug pump 10 sx cement at 40 to -5'.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:15 p.m. Day: 28 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with mud,

2nd plug pumped 25 sx cement at 1780',  
3rd plug pumped 45 sx cement at 700',  
4th plug pumped 10 sx cement at 40 to -5'.

RECEIVED  
KANSAS CORPORATION COMMISSION  
5-12-93  
MAY 12 1993  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used common cement by Sargent & Horton. Recovered 855' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

DATE: 5-12-93  
observe this plugging.

INVOICED  
DATE: 5-12-93  
INV. NO. 37679  
4-28

Signed Glenn R. Barlow  
(TECHNICIAN) RWJ