

189-00026-0001 R

To: 1 060709
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-~~AA~~ Comp 5-5-61

C SW SE SEC. 1, T 31 S, R 35 W 18

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobile Oil Corp.

Name & Address P.O. Box 5444

Denver Colo.

80217

Loose Name Cutter Well # 1 Input

County Stevens 226.79

Well Total Depth 6978 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1736

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Patrick Well Services Inc. license Number 7547

Address 852 Petoskey road Box 1273 Liberal, Kansas 67901

Company to plug at: Hour: 10:00 AM Day: 4 Month: November Year: 1985

Plugging proposal received from Ron Wilson

(company name) Mobile Oil Corp. (phone) 316-624-4901

were: Packer & tubing in hole top @ 1550'. Recovered 1550' of 5 1/2" casing. They set 6977' of 5 1/2" casing. Plug back TD-5345'. Pump down 8 5/8" to get flow rate. Then pump cement to fill hole from TD to surface.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 PM Day: 4 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st run tubing with sledge & got back on 5 1/2"

casing got flow rate of 3 Bbls per min. w/ 100# pump pressure.

Pumped 454 sbp cement w/ 8 5/8" shut in w/ hole full of fluid. Waited for cement to set up.

2nd backed tubing off leaving 120' in hole. Ran tubing back in hole to 1430' & pumped 275 sbp cement filling hole

Remarks: to 0'. No fall back on cement. good returns. There wasn't a plugging application filed at this date. They were trying to recomplete well when they ran in to this problem. wanted to plug while rig was on hole. observe this plugging.

INVOICED

DATE 12 9 - 85

INV. NO. 11339 11-4

RECEIVED
STATE CORPORATION COMMISSION
Signed Paul A. Luthi
(TECHNICIAN)

the orders. NOV 8 1985 JAN 16 1986

DEC 16 1985

11-8-85
CONSERVATION DIVISION