

1 050987

1-18-88

API NUMBER 15-189-21,146-0000

SW NW, SEC. 10, T 31 S, R 35 W/EX

3300 feet from S section line

4620 feet from E section line
"A"

Lease Name Margaret Jordan Well # 1

County Stevens 190.13

Well Total Depth 5850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1810

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobil Oil Corporation

Name & Address P.O. Box 5444

Denver, CO 80217

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Unit Drilling Company License Number 9137

Address P.O. Box 702500, Tulsa, OK 74170

Company to plug at: Hour: 2 p.m. Day: 18 Month: 1 Year: 19 88

Plugging proposal received from Steve Lewis

(company name) Mobil Oil Corporation (phone) 303-298-2047

was: to fill hole with heavy mud and spot cement through drill pipe Elevation 2992' GL

1st plug at Chase Group with 100 sx cement, 2nd plug at 1810' with 50 sx cement,

3rd plug at 750' with 25 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 7 p.m. Day: 18 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2900' with 100 sx cement,

2nd plug at 1810' with 50 sx cement,

3rd plug at 750' with 25 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED
(XXXXXX) observe this plugging.

DATE 1-25-88

INV. NO. 19636

1-18

FEB 24 1988

Signed Richard W. Lacey
(TECHNICIAN)

STATE CORP.
JAN 21 1988
1-21-88
CONSERVATION DIVISION
Wichita, Kansas