

2 040252

R 2775-90

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150 E 5th SW, SEC. 34, T31 S, R 5 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20127-00-01

660 feet from N/S section line
4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7744 Lease Name Barby-Coslett Well # 1-34

Operator Name & Address: Sho-Bar Energy Inc. County Harper 109.53

Bx 217 Well Total Depth 3370 feet

Harper Ks. 67058 Conductor Pipe: Size _____ feet

Howard Short Surface Casing: Size 8 7/8 feet 217

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Pratt Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Howard Short

(company name) Sho-Bar Energy (phone) _____

were: _____

4 1/2 3370' Sand to 3250' 5 sk.
Perf. 3303' Top. 5 hull 15 gel 110 sk

Plugging Proposal Received by J. Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1520 Day: 13 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT Pratt Well Service dumped sand inside

the 4 1/2 casing to 3250' to cover the perforations and
spotted 5 sacks of cement thru the dump bailer on top of
sand. The 4 1/2 was shut-off and recovered from 2550'. The
top was squeeze plugged thru the 8 7/8" surface casing. 3 sks
of hulls, 15 sks of gel and 110 sacks of cement

Remarks: HOWCO 3.5/422 SI 400# MX 600#

If additional description is necessary, use BACK of this form.)

INVOICED

I (did) / (did not) observe this plugging. RECEIVED
STATE CORPORATION COMMISSION

DATE FEB 27 1986

INV. NO. 12726

W

FEB 26 1986 2-26-86

Signed Steve Anderson
(TECHNICIAN)