

To: 1 020432 1-27  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-119-20,273-0000 147R

S/2 S/2 SE, SEC. 6, T. 31 S, R 29 W/E

330 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4480

Lease Name Bridges Well # 1

Operator: Blackhawk Exploration  
Name & Address 200 E. 1st #100 LL  
Wichita, KS 67202

County Meade 195.00

Well Total Depth 6000 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1581

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 24 Month: 1 Year: 19 92

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5516' w/200 sx cement, PBTD 5516', Perfs at 5401-23'

1st plug pump 20 sx cement on bottom,

2nd plug pump 50 sx cement at 1620',

3rd plug pump 35. sx cement at 650',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 27 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pump 1 1/2 sx hulls and 20 sx cement at perfs, loaded hole w/mud,

2nd plug pumped 50 sx cement at 1620',

3rd plug pumped 35 sx cement at 650',

4th plug pumped 10 sx cement at 40' to -4'.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1992  
1-30-92  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2807' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
(if additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE 2-12-92

Signed Glen R. Barber  
(TECHNICIAN)

INV. NO. 34514  
1-27 MAR 17 1992