

To: 1 040498  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-17

API NUMBER 15- 119-20,822-0000 1 H&R R

SW SE SW, SEC. 22, T 31 S, R 29 W/EX  
330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8802

Lease Name Pennington "22" Well # 1

Operator: Cobra Oil & Gas

County Meade 187.20

Name & Address P.O. Box 1929

Well Total Depth 5760 feet

Woodward OK 73082

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1500

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sage Drilling Company License Number 5421

Address 202 S.St. Francis, Wichita, KS 67202

Company to plug at: Hour: 9:45 a.m. Day: 17 Month: 1 Year: 19 91

Plugging proposal received from Glenn Waugh

(company name) Cobra Oil & Gas (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1360'

1st plug at 1520' with 50 sx cement, 2nd plug at 680' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 12:30 p.m. Day: 17 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement,

2nd plug at 680' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 2-11-91

INV. NO. 30647

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
1-25-91  
JAN 25 1991  
CONSERVATION DIVISION  
Wichita, Kansas