

1 060398

15-189-20696-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

NE NE, SEC. 28 ; T 31 S, R 35 (W/E)

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6958

Lease Name Brollier Well # 28-1

Operator: Flynn Energy Corp.

County Stevens 198.25

Name & Address R. R. 1

Well Total Depth 6100 feet

Hennessey, OK 73742

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1725

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 9 Month: November Year: 19 84

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" set at 6100' PBD 6030' Perfs at 6014-20'

1st plug pump 1 sack hulls and 20 sx cement to bottom

2nd plug at 3028' with 25 sx cement

3rd plug at 1780' with 25 sx cement

4th plug at 680' with 20 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthie
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 am Day: 9 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 6100' PBD 6030' Perfs at 6014-20'

1st plug pumped 1 sack hulls and 20 sx cement to bottom, 2nd plug at 3028' with 25 sx

cement, 3rd plug at 1780' with 25 sx cement, 4th plug at 680' with 20 sx cement, 5th &

6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECOVERED Remarks: Recovered 3028' of 4 1/2" casing. Used common sacked cement by Sargent's.

STATE CORPORATION COMMISSION (If additional description is necessary, use BACK of this form.)

11-15-84

NOV 15 1984 (do not) observe this plugging.

INVOICED

Signed Paul A. Luthie (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

DATE 11-20-84

INV. NO. 4887

DEC 07 1984

FORM CP-2/3
Rev. 01-84