

1 020362

3-19

165

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,548-0000

C NE SE, SEC. 28, T 31 S, R 35 W&E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30631

Lease Name Brollier Well # 28-1

Operator: Kansas Exploration Inc.

County Stevens 201.50

Name & Address P.O. Box 681

Well Total Depth 6200 feet

Liberal, KS 67905-0681

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1746

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10:30 a.m. Day: 15 Month: 3 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 6190' w/100 sx cement, Perfs at 6030-6035'

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1991
3-22-91
CONSERVATION DIVISION
Wichita, Kansas

1st plug pump 1 sx hulls and 20 sx cement at perfs,

2nd plug pump 35 sx cement at 2500', 3rd plug pump 50 sx cement at 1780',

4th plug pump 35 sx cement at 700',

5th plug pump 10 sx cement at 35-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5 p.m. Day: 19 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,

2nd plug pumped 35 sx cement at 2500',

3rd plug pumped 50 sx cement at 1780',

4th plug pumped 35 sx cement at 700',

5th plug pumped 10 sx cement at 35-0'.

Remarks: Used common cement by Sargent's. Recovered 2516' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(old # 31278) observe this plugging.

DATE 4-2-91

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 31278

3-19 MAY 03 1991