

1020812 10-27 API NUMBER 15- Spudded 1963 189-10038-0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW SE NE SW, SEC. 3, T 31 S, R 37 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

1880 feet from S section line
2080 feet from W/E section line
Lease Name Parsons "B" Well # 1
County Stevens 98.80
Well Total Depth 3040 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 655

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Anadarko Petroleum Corp. License Number 4549

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 9 a.m. Day: 26 Month: 10 Year: 19 94

Plugging proposal received from Jack Tuman

(company name) Anadarko Petroleum Corp. (phone) 316-544-7240

were: 5 1/2" at 3040' with 185 sx cement, PBTD 2768', Perfs at 2453-2676'
1st plug pump 2 sx hulls and 25 sx cement from 2453-2300',
2nd plug spot 35 sx cement at cut off, 3rd plug spot 50 sx cement at 650-550',
4th plug spot 18 sx cement at 53-3'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 27 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs. Let set 2

hours, pressured to 700#,
2nd plug pumped 50 sx cement at 700',
3rd plug pumped 20 sx cement at 60 to -4'.
Cement dropped 60'. Filled to surface with Redi-Mix.

Remarks: Used Class H cement by Halliburton. Recovered 723' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired) observe this plugging.

DATE 11-7-94
INV. NO. 41582
10-27

Signed Glenn R. Barlow (TECHNICIAN)

