

To: 100189
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

1-15

API NUMBER 15 Spud date 2/37 15-189-16148-0000

C SW, SEC. 33, T 31 S, R 38 XX

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Cavner Well # 1-25

Operator: Anadarko Petroleum Corporation

County Stevens 85.74

Name & Address P.O. Box 351.

Well Total Depth 2638 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 557

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 13 Month: 1 Year: 19 98

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

was: 7" at 2424' w/100 sx cement, 5 1/2" slotted liner 2424-2638'

1st plug set CIBP at 2408' with 3 sx cement on top, pull stretch,

2nd plug pump 75 sx cement, displace to 585',

3rd plug pull casing to 40', pump 15 sx cement.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 15 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2408' with 3 sx cement on top,

2nd plug pumped 75 sx cement, displaced to 585',

3rd plug pulled casing to 40', pumped 15 sx cement to top off.

Remarks: Used common cement by Sargent & Horton. Recovered 585' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 28 1998

INV. NO. 49986

Signed Gary Winters
(TECHNICIAN)