

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22351-00-00
Spot: NWSW Sec/Twnshp/Rge: 33-31S-38W
1980 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: CAVNER A Well Number: 5
County: STEVENS Total Vertical Depth: 620 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet:
Operator Name: ANADARKO PETROLEUM CORPO Surface Casing: Size 8.625 feet: 20
Address: 1701 NORTH KANSAS AVE Production: Size _____ feet: 35.00
LIBERAL, KS 67905 Liner: Size _____ feet:

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 12/01/2000 11:00 AM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: FRED GRESS Company: ANADARKO Phone: (316) 624-6253

Proposed Plugging Method: PUMP CMT FROM 620' TO SURFACE. RUN 1 JOINT OF 8 5/8 AS MARKER.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/05/2000 10:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

ON 12/01/00 HILTON HIXON ON LOCATION. RAN TUBING TO 642' AND SPOT 50 SX 60/40 POZMIX 6% GEL 3% CC. TAGGED AT 240'. RAN 50 SX CMT. ON 12/04/00 RAN TUBING. TAGGED CMT AT 182'. PULLED TUBING OUT OF HOLE. FOUND CMT IN LAST JOINT. RAN TUBING TO 176'. HALLIBURTON PUMPED 400 SX CMT. DID NOT CIRCULATE. LET SET OVERNIGHT. ON 12/5/00 RAN TUBING IN HOLE. TAGGED CMT AT 100'. PULLED TUBING OUT OF HOLE. RAN 90' BACK IN. HALLIBURTON PUMPED 50 SX FIX-A-TROPIC. CIRCULATED CMT TO SURFACE. SHOVED 1 JOINT OF 8 5/8" CASING 20' IN HOLE TO MARK.

Remarks: USED 60/40 POZMIX 6% GEL 3% CC & 50 SX OF FIX-A-TROPIC CMT. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed _____

RECEIVED
STATE CORPORATION COMMISSION

(TECHNICIAN)

DEC 7 2000
12-7-00
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 12/7/00
DEC 06 2000
WV, NC 20010610831P

