

To: 100102 3-7
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
1305 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 6/17/85-189-30097-0000
W/2 W/2 NW, SEC. 34, T 31 S, R 38 W/8
3960 feet from S section line
5080 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name McClure H Well # 2
County Stevens 98-15
Well Total Depth 3020 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 638

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services Inc. License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 7 Month: 3 Year: 19 97

Plugging proposal received from Fred Cress

(company name) Anadarko Petroleum (phone) 316-544-7240

were: 5 1/2" at 3019' w/200 sx cement, PBSD 3002', Perfs at 2768-2936' (10 sets) TOC 1800'

1st plug set CIBP over perfs with 2 sx cement on top,

2nd plug perforate casing at 687-694' and circulate cement.

3-12-97

RECEIVED
MAR 12 1997
STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 a.m. Day: 7 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2700' with 2 sx cement on top,

Perforated at 687-688' - 4 shots - circulated with mud,

2nd plug pumped 250 sx cement down 5 1/2", circulating cement to surface, leaving 5 1/2" casing full to surface.

Remarks: Used common cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE / Bill to observe this plugging.

DATE MAR 12 1997

INV. NO. 47738
3-7

Signed Gary White (TECHNICIAN)