

To: **1020800** **9-15**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 129-00082-0000  
C NE SW, SEC. 7, T 31 S, R 39 W, XX  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5952

Lease Name Morgan GU CG Well / 1

Operator: Amoco Production Company

County Morton

Name: Amoco Production Company

Well Total Depth 6110 198.57 feet

Address P.O. Box 800

Conductor Pipe: Size            feet

Denver, CO 80201-0800

Surface Casing: Size 9 5/8" feet 723

Abandoned Oil Well            Gas Well X Input Well            SWD Well            D&A           

Other well as hereinafter indicated           

Plugging Contractor Amoco Production Company License Number 5952

Address P.O. Box 800, Denver, CO 80201-0800

Company to plug at: Hour: 2 p.m. Day: 15 Month: 9 Year: 1994

Plugging proposal received from Melanie Hill

(company name) Amoco Production Company (phone) 316-356-7059

logs: 4 1/2" at 2907' w/220 sx cement, TOC 2150', PBSD 2834', Perfs at 2710-2796'

1st plug set CIBP at 2834',

2nd plug set CIBP at 1197' and dump 2 sx cement on top with bailer, sand in to 1930',

3rd plug perforate at 750-52', circulate cement to surface.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part            None           

Operations Completed: Hour: 4:30 p.m. Day: 15 Month: 9 Year: 1994

ACTUAL PLUGGING REPORT Hole in 4 1/2" at Glorietta

1st plug set CIBP at 2834',

2nd plug set CIBP at 1197' and dump 2 sx cement on top with bailer, sanded in to 1930'

3rd plug perforated at 750-52', circulated cement to surface.

Remarks: Used 60/40 Pozmix 6% gel Class H cement by Halliburton. No casing recovery.

**INVOICED**

(If additional description is necessary, use BACK of this form.)

DATE 9-28-94

Signed Glenn R Barlow  
(TECHNICIAN)

INV. NO. 41288