

To: 1 020799 9-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- WA 129-00502-0000
C, SEC. 8, T. 31 S, R. 39 W/8
2640 feet from S section line
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Gillespie Gas Unit 1

Operator: Amoco Production Co.

County Morton

Name & Address P.O. Box 800

Well Total Depth 2645 85.96 feet

Denver, CO 80201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Amoco Production Co. License Number 5952

Address P.O. Box 800, Denver, CO 80201

Company to plug at: Hour: 8 a.m. Day: 16 Month: 9 Year: 19 94

Plugging proposal received from Melanie Hill

(company name) Amoco Production Co. (phone) 316-356-7059

vers: 5 1/2" at 2611' w/350 sx cement, 4" liner 2387-0' cemented to 0', Perfs at 2421-2586'

1st plug set CIBP at 2140',

2nd plug run 2 3/8" tubing and tag CIBP, circulate cement to surface with 85 sx,

3rd plug hook onto 8 5/8", pressure up, pull tubing and fill 4" liner to surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 16 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2140',

2nd plug ran 2 3/8" tubing and tagged CIBP. Circulated cement to surface with 85 sx,

3rd plug hooked onto 8 5/8" and pressured up to 1200 psi. Pulled tubing and filled 4" liner to surface with cement.

Remarks: Used 60/40 Pozmix 6% gel Class H cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 9-28-94

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 41286